## Validation de systèmes à vide pour le grand arrêt numéro 1 du LHC

#### Gregory CATTENOZ, CERN, TE-VSC group, on behalf of LHC Beam Vacuum section

Journées thématiques : « Problématiques Ultravides d'aujourd'hui sur les installations complexes » Institut Néel CNRS, Grenoble, 1er et 2 Décembre 2014



# Outline

- Introduction
- Presentation of the vacuum validation process
- LHC beam vacuum consideration
- 3 tests overview:
  - Pump down
  - Residual Gas Analysis
  - Internal leak rate measure
- Example of the Totem roman pot detector
- Conclusion and outlook



# Introduction

#### Vacuum baseline:

VACUUM VALIDATION → LHC BEAM VACUUM INSTALLATION

Measure and verification of vacuum performance

- Functionality
- Leak tightness
- Outgassing rate
- Residual Gas Analysis
- Leak tightness
- Functionality

#### Parts tested

Instruments: TCTP collimators, MKI, Roman pots,...etc. Gauges, valves, VPI, NEG cartridge...etc.



- Before bake out cycle

- After bake out cycle

# **Organisation flux**

#### **Coordination : G. Cattenoz**



### LS1 Vacuum validation: Noticeable activities

- Scheduling: Procurement Vs installation time
- Coordination: Staff
- Laboratory work
- Reception + preparation
- Bake-out cycle
- Tests and validation
- Official reporting : EDMS +
  LBV section web site





### LS1 vacuum validation: Some numbers

- 2 laboratories: active/nonactive parts
- > 19 test benches: LHC + Experience
- > 18 months activity
- > 3 (+1) staff



CERN vacuum laboratory B.113



## **Examples of tested parts**

















## Examples of tested parts















## LHC Beam vacuum consideration

#### Pressure requirements:

**LHC**: Pmax  $\approx 10^{-8}$  mbar - 100h beam life time operation **Experiments**:  $10^{-10}/10^{-11}$  mbar - reduced background

Pumping characteristics

Room temperature vacuum sectors VPI: every 28m - CH<sub>4</sub> NEG: coating/strip/cartridge - H<sub>2</sub>, CO, CO<sub>2</sub> Arcs and standalone: Cryo-pumping

Rely on NEG pumping → Localized outgassing rate: Necessity to control quantity and nature of residual species after bake out.



### How to achieve vacuum performance?

- 1. UHV clean, vacuum treated parts
- 2. Tested/known sub-components
- 3. Test bench zero reference
- 4. Controlled bake-out: Instrumentation, cold point, cycle



Vacuum-fired ferrite (TT2-111R / Transtech) @1000°C/24h00 → TCTP + XRPT





#### Certificat de coulée acier inox pour fabrication cable BPM (TMS)





### Preliminary test: Pump down





### Preliminary test: Pump down



Diagnostic possible presence of contaminants or leak by comparison

Metallic substrate: P(t) fitted with 1/t equation



### Internal outgassing rate measurement 1/2





### Internal outgassing rate measurement 2/2

#### Procedure could be applied in case of active NEG present in the system



Q<sub>[air eq.]</sub><5.10<sup>-9</sup> mbar.I/s correspond to ≈ 1 m saturated NEG (80mm D.) every 150 days



# RGA acceptation criteria 1/2

#### Based on collimator specifications (EDMS 1113402)

- Maximum total outgassing rate of 2.10<sup>-7</sup> mbar.l/s after bake out
- Presence of known residual gas in well-defined limits

#### Why?

- Control absence of contaminants + air leaks
- Verify partial pressure composition after bake out



#### How?

- RGA currents normalized to H<sub>2</sub>: Dominant gas but not affecting NEG performance
- Acceptation limits template applied to normalized RGA currents



# RGA acceptation criteria 2/2

Normalised RGA currents to H<sub>2</sub> with defined acceptance limits





## **Example of XRPT stations**







# **XRPT station: Critical bake-out**







# **XRPT station: Leak on BPM**



YEARS / ANS CERN

## **XRPT station: Final results**

Outgassing rate after bake out cycle at 250°C≈ 6,0.10<sup>-9</sup> mbar.l/s.





### **XRPT: Conclusion based on LS1 experience**

For bake out, ensure: (can not be neglected)

- Proper positioning of:
  - Regulating thermocouple
  - Appropriate heating element
- No cold point

guarantee correct temperature regulation

- ➢ Correct operation → Regular check to 50°C, 100°C, until maximum temperature
- > Removal of equipment, always after bake out cycle, to enable helium leak test

#### In any circumstance, allow TIME for test!



## Conclusions

- All parts tested before installation
  → <u>RESPECTED BASELINE</u>
- Overall 1200 parts tested

| Equipment                                | XRPT                        | Collimator | Beam<br>instrument<br>BTV | Sector<br>valve (MKI) |
|--|-----------------------------|------------|---------------------------|-----------------------|
| Average Q_tot.<br>measured<br>[mbar.l/s] | <b>2.0.10</b> <sup>-8</sup> | 3.0.10-8   | 4.0.10 <sup>-9</sup>      | 1.5.10 <sup>-8</sup>  |

 About 5% non conformity: TCSP, BQSV.5R4, BWS.5R4, TDI blocs, insert, VPIAN



Non-conformities distribution



## **Outlook and further development**

#### General/logistics:

- Put in place tool to identify components at reception
- Use of EDMS as tool for report results acknowledgement
- Take part in the conceptual phase, prototyping and follow fabrication of critical component

#### Measures:

- Review acceptance criteria
- Allow time to carry out sub-assembly test of complete system (i.e. Roman pot)
- Perform regular zero measurement of test bench
- Operate recurrent RGA calibration





# More details on this subject

Proceedings of IPAC2014, Dresden, Germany

WEPME041

#### VACUUM ACCEPTANCE TESTS FOR THE UHV ROOM TEMPERATURE VACUUM SYSTEM OF THE LHC DURING LS1

G. Cattenoz, V. Baglin, G. Bregliozzi, D. Calegari, J. Gallagher, A. Marraffa, and P. Chiggiato European Organization for Nuclear Research, CERN, 1211 Geneva 23, Switzerland



#### Thank you for your attention



